Capsule Summary SM-599 Barn at Part of Cross Manor Beachville vicinity Private

c. 1860-1870

Situated on an agricultural tract that was once part of "Cross Manor," this modest, axial plan tobacco barn features many details that are typical for the building type and period. The framing is mortise-and-tenoned, the members are hewn and circular sawn, and cut nails were used for fasteners. The oral tradition surrounding the barn, however, is anything but typical.

According the current owner Phillip Meagher, the barn was used by local African-American residents of Beachville as a meeting place and dance hall in the late-nineteenth century. Curiously, architectural evidence supports this local tradition. The shed side walls of the barn, for instance, are sheathed with vertical, circular sawn boards that have been whitewashed. Normally exhibiting a dirt floor, the barn utilizes plank floors. Further research is needed to ascertain the full significance of this otherwise conventional looking building.

SM-599, Barn at Part of Cross Manor St. Mary's County Maryland Comprehensive State Historic Preservation Data

<u>Historic Context</u> Geographic Organization:

Western Shore

Chronologicial/Developmental Period:

Industrial/Urban Dominance, 1870-1930

Historic Period Theme:

Architecture

Agriculture Social/Education/Cultural

Resource Type Category:

Building

Historic Environment:

Rural

Historic Function and Use:

Tobacco Barn

Known Design Source:

None

- Maryland Historical Trust HISTORIC PROPERTIES State Historic Sites Inventory Form

MARYLAND INVENTORY OF

Surve	еу мо.	3.1739
Magi	No.	
DOE	yes	no

1. Nam	e (indicate pr	referred name)	· <u></u>	
historic Barr	n at Part of Cross Mano	r (pref.)		
and/or common	Meagher Barn			
2. Loca				
street & number	N side of Beachville	Rd, approx 1 mile W of int	ersection of Beachvill	& Route 5 e not for publication
city, town Bea	chville	_x_ vicinity of	congressional district	1
state Maryland		county S	St. Mary's County	TM-67, B-9, P-77
3. Clas	sification			
Category district building(s) structure site object	Ownership public private both Public Acquisition in process being considered x not applicable	Status occupiedX unoccupied work in progress AccessibleX yes: restricted yes: unrestricted no	Present Use _x agriculture commercial _ educational _ entertainment _ government _ industrial _ military	museum park private residence religious scientific transportation other:
4. Own	er of Prope	rty (give names an	d mailing addresse	es of <u>all</u> owners)
name Philli	p E. Meagher, Jr.			
street & number	PO Box 186		telephone n	o.:
city, town St	. Inigoes	state	and zip code Md 20)684-0186
5. Loca	ation of Leg	al Description	n	
courthouse, regi	istry of deeds, etc. St	. Mary's County Courthouse)	liber MRB 409
street & number				folio 333
city, town Leo	nardtown		state	Md
6. Rep	resentation	in Existing	Historical Surv	zeys
title				
date			federal sta	te county loca
depository for s	urvey records		· · · · · · · · · · · · · · · · · · ·	
city, town			state	

7. Desc	cription		Survey No	°• SM-599
Condition excellent goodX_ fair	deteriorated ruins unexposed	Check one unalteredX altered	Check one original site moved date of move	

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Contributing Resource Count: 1

7. Description

The Barn at Part of Cross Manor lies on the north side of Beachville Road approximately 0.4 of a mile west of the intersection of Beachville Road and Maryland Route 5, near St. Inigoes, Maryland. Situated in the midst of a soybean field well off the road, this agricultural building is oriented on a north/south axis. A non-contributing one story, ranch-style dwelling is located to the west of the barn and lies perpendicular to a dirt drive that extends from the road. The barn, house, and field are part of a 31.77 acre parcel that is ringed by a series of wooded tracts.

The Barn at Part of Cross Manor, constructed c. 1860-1870 is a frame, tripartite tobacco barn composed of an axial plan center block with sheds descending off of its east and west sides. The barn's braced frame rests on a brick pier foundation. The exterior walls are sheathed with vertical boards fastened to the frame with mature cut and wire nails. The cornice is open and the roof is covered with corrugated metal. Judging from architectural evidence, it appears the west shed was constructed subsequent to the main block and east shed.

The south elevation consists of the barn's gable end. A centrally located door hung on modern hinges provides access in the main block. Part of the original door lies just above this entry and remains attached to a strap hinge. A door, now removed, once provided entry into the west shed. The asymmetrical roofline observed on the elevation represents the first hint that the sheds were constructed at different times. Architectural evidence, namely the circular sawn framing members and the use of wire nails, provide an early twentieth century date for the west shed while the east shed dates to the barn's initial construction. The east elevation consists of the largely open east shed that is only partially sheathed with vertical boards. The north elevation contains only a single doorway into the main block. Like the east elevation, the west elevation is only partially sheathed with vertical boards as it features an unbarred opening.

The barn's interior deviates from typical tobacco barn construction practices. The most significant difference is its plank floor. The floor is suspended by a series of large transverse joists that are hewn. The joists lie on sills that in turn are supported by the brick piers. Other than the floor, the framing of the barn follows period conventions. It consists of hewn, circular sawn, and pit-sawn members that are mortise and tenoned together. The framing lies irrespective of the seven five-foot rooms created by the horizontal tobacco poles. Three tiers of poles, a tier of common ties, and two tiers consisting common rafter collars were all used to hang tobacco. In order to bridge the width of the main block, "swinging tiers" suspended from the hewn common ties were utilized. The common ties also support the circular sawn false plate. This thin plate supports the feet of the common rafters. Each rafter pair is joined by two common rafter ties and again at the peak with a half-lap joint.

A second interesting feature is seen on the east side of the main block where a series of vertical, circular sawn planks have been fastened to nailers and then whitewashed. Nailing patterns seen on the outside face of the main block's west side indicate that boards also existed on this side until they were removed. Oral tradition has suggested that these vertical boards and aforementioned floor are evidence that local African-American residents of Beachville may have used the barn as a meeting and dance hall.

X 1800–1899 commerce exploration/settlement philosophy theater 1900- communications industry politics/government transports invention other (specific dates Specific dates	0. 3	ign	ncance		<u></u>		અ	irvey No.	SM-599	
check: Applicable Criteria: x A B x C D and/or	prehis 1400- 1500- 1600- 1700- _X 1800-	-1499 -1599 -1699 -1799 -1899	archeology-prel archeology-hist x agriculture architecture art commerce	nistoric oric s	communit conservat conservat economic education engineerii exploratio	y planning ion s ng n/settlemen	lav lite mi mi mi mt ph	v erature litary usic ilosophy		_ science _ sculpture _ social/ humanitarian _ theater _ transportatio
	Specific	dates		Bu	iilder/Archi	itect	14.7			
Level of Significance: national state x local	check:	ar Appli	d/or cable Exception	A	BC	D				
Prepare both a summary paragraph of significance and a general statement of history a	Prepare				-				ent of 1	history and

Situated on an agricultural tract that was once part of "Cross Manor," this modest, axial plan tobacco barn features many details that are typical for the building type and period. The framing is mortise-and-tenoned, the members are hewn and circular sawn, and cut nails were used for fasteners. The oral tradition surrounding the barn, however, is anything but typical. According the current owner Phillip Meagher, the barn was used by local African-American residents of Beachville as a meeting place and dance hall in the late-nineteenth century. Curiously, architectural evidence supports this local tradition. The shed side walls of the barn, for instance, are sheathed with vertical, circular sawn boards that have been whitewashed. Normally exhibiting a dirt floor, the barn utilizes plank floors. Further research is needed to ascertain the full significance of this otherwise conventional looking building.

9. Major Bibliographical References

Survey No. SM-599

See Significance 8.0.

10. Geograp	hical Data			
	rty 1 acre around barry's City	rn	Quadrangle	e scale1:24 000
UTM References do NOT	complete UTM refer	ences		
Zone Easting	Northing	B Zone E	esting	Northing
c				Lililii
EL, LI,		F		
G		H		
Verbal boundary description are as per deed description	1.			
me as per deed description List all states and counti	1.	apping state or coun	ty boundaries	code
	es for properties overl		ty boundaries	code
me as per deed description List all states and counti state	es for properties overl code	county	ty boundaries	
List all states and counting state 11. Form Pro	es for properties overl code code	county	ty boundaries	
me as per deed description List all states and counting State 11. Form Propagate State Kirk E. Ranze	code code code pared By etta, Historic Sites Sur	county	ty boundaries 8-18-98	
List all states and counting state 11. Form Propagation St. Mary's Counting and St. Mary's Counting a	code code code pared By etta, Historic Sites Sur	county	8-18-98	code

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to:

Maryland Historical Trust Shaw House 21 State Circle Annapolis, Maryland 21401 (301) 269-2438

MARYLAND HISTORICAL TRUST DHCP/DHCD 100 COMMUNITY PLACE CROWNSVILLE, MD 21032-202° -514-7600 SM-599, Barn at Part Cross Manor

St. Mary's County 8.1 Significance

Chain-of-Title

(All deeds are located at the Land Records Office, St. Mary's County Courthouse, Leonardtown, Maryland unless otherwise noted.)

Reference: Liber MRB 409, Folio 333

Grantee: Philip E. Meagher, Jr. and Teresa L. Meagher

Grantor: James and Mable N. Parrott

Date: May 2, 1988

Notes: The property is listed as containing 31.77 acres.

Reference: Liber MRB 46, Folio 39 Grantee: James and Mable N. Parrott

Grantor: James and Mable N. Parrott and Walter L. Cummings and Charles T. Ford

Date: June 21, 1979

Reference: Liber CBG 169, Folio 499

Grantee: James Parrott, Walter L. Cummings, Charles T. Ford

Grantor: Stanley and Ella M. Chemachi

Date: July 14, 1971

Reference: Liber CBG 108, Folio 280 Grantee: Stanley and Elsa M. Chemachi Grantor: Thomas W. and Mary Rita Owens

Date: July 17, 1963

Notes: Here the property is listed as containing 41.424 acres.

Reference: Liber CBG 80, Folio 480 Grantee: Thomas W. and Mary Rita Owens Grantor: Emerson R. and Grace E. Taylor

Date: April 24, 1959

Notes: The deed notes a plat by McCrone, Inc. dated July 1963.

Reference: Liber CBG 13, Folio 507 Grantee: Emerson and Grace E. Taylor

Grantor: Stephen H. Bean Date: September 9, 1942

Notes: The property is listed as containing 44 acres and is called "Part Cross Manor."

Reference: Liber EBA 10, Folio 85

Grantee: Stephen H. Bean Grantor: Joseph H. Ching Date: February 21, 1912

Notes: As a result of a decree by the circuit court dated December 27, 1911, the property is sold at auction for \$1125. The case was between Joseph H. Ching and Sarah E. Smallwood, James Smallwood, and Bernard Smallwood and is located in Decree Record EBA 5, Folio 1. According to the court documents, John R. Smallwood was to pay \$850 to Allen C. Tyler for the property.

SM-599, Barn at Part Cross Manor St. Mary's County 8.2 Significance

(cont.)

Tyler died, however, before Smallwood could fully repay Tyler and so a deed was never executed. In 1902, a deed was executed between Smallwood and Daniel C. Hammett, the executor for Allen C. Tyler. Smallwood, however, died before he could make full payment on the property, so his heirs were forced to sell the property.


Reference: Liber EBA 2, Folio 438

Grantee: John R. Smallwood

Grantor: Daniel C. Hammett, Administrator of Allen C. Tyler's estate

Date: July 22, 1902

Notes: The absence of a bean clause does not permit a more in-depth look at the past property owners. Research on the surrounding properties, however, suggest that Tyler's tract was once part of the larger Cross Manor. It is unclear when it was subdivided. Judging from the evidence of the existing barn and descriptions of the house that was demolished, it may have been between 1840-1860.





M. 599 Boin at late on an St. Mary's lounty Kick Ranzetta rd stro 5 elevation 362



5 M- 599 Barn at Part of Cross Manon St Mary's County Kirk Ranzetta Nov, 1997 Md SHPO Interior - look on N